


SECTION VIEW

NOTES:

1. ALL PICP SHALL CONFORM TO ASTM C936 AND ADA DESIGN GUIDELINES.
2. SLOPE OF SOIL SUBGRADE SHALL BE 0.5% OR LESS, MAXIMUM PICP SURFACE SLOPE SHALL BE 6%.
3. THE SEASONAL HIGH WATER TABLE SHALL HAVE A MINIMUM 2 FT SEPARATION FROM THE BOTTOM OF THE AGGREGATE SUBBASE.
4. IN HSG B, C, OR D SOILS, THE SURFACE OF THE SUBGRADE UNDER INFILTRATING PICP SYSTEMS SHOULD BE SCARIFIED, RIPPED, OR TRENCHED IMMEDIATELY PRIOR TO AGGREGATE SUBBASE PLACEMENT TO MAINTAIN PRE-CONSTRUCTION SUBGRADE INFILTRATION RATE.
5. THE INCLUSION OF AN UNDERDRAIN SYSTEM WITH IMPERMEABLE LINER (INCLUDING BOTTOM LAYER) IS DEPENDENT UPON THE RESULTS OF THE GEOTECHNICAL INVESTIGATION CONSISTENT WITH THE GUIDANCE PROVIDED IN THE NCDEQ STORMWATER DESIGN MANUAL AND CITY OF RALEIGH DESIGN MANUAL. IMPERMEABLE LINER SHALL BE HDPE, PVC, OR LDPE AND SHOULD BE INSTALLED SO THAT LINER EXPOSURE TO SUNLIGHT IS MINIMIZED.
6. ELEVATION GRADIENT BETWEEN THE CONCRETE GUTTER AND ADJACENT PICP SHALL NOT EXCEED 1/4"; OTHERWISE, PROVIDE 1:2 BEVEL ON EDGE OF GUTTER.
7. OPEN VOID FILL MEDIA AROUND PICP SHALL BE LARGER OF NO. 8, NO.9, OR NO. 89 STONE, WASHED AND FREE OF FINES, SUITABLE FOR PLACEMENT IN JOINT SIZE SPECIFIED BY MANUFACTURER.
8. BOTH PIPE PENETRATIONS AND ATTACHMENT OF 30 MIL IMPERMEABLE LINER TO CONCRETE CURBS (USING CONCRETE ANCHORS SPACED AT MAXIMUM 18" O.C. AND BATTEN STRIPS) SHALL BE DONE IN ACCORDANCE WITH ASTM 6497.
9. ALL AGGREGATE SIZED ACCORDING TO ASTM C136.
10. AASHTO LAYER COEFFICIENTS FOR OPEN-GRADED BASE AND SUBBASE SHALL RANGE BETWEEN 0.06 AND 0.10.
11. AASHTO MINIMUM LAYER COEFFICIENT OF 0.3 FOR PAVER AND BEDDING LAYERS IS RECOMMENDED.
12. LOCATE UNDERDRAIN AS SHOWN ON THE IMPROVEMENT PLANS. HORIZONTAL LOCATION MAY VARY WITHIN PAVEMENT SECTION AS LONG AS MINIMUM OFFSET DISTANCES AND BOTTOM SLOPES ARE MAINTAINED.
13. DEPTH OF PERFORATED PVC PIPE MAY BE ADJUSTED TO TIE INTO THE ADJACENT DRAINAGE INFRASTRUCTURE AS NEEDED.
14. ALTERNATE BOTTOM PROFILE OMITTING THE INSET TRENCH MAY BE USED AT DIRECTION OF ENGINEER SO LONG AS 1% MIN SLOPE TO UNDERDRAIN IS RETAINED.
15. ALL MATERIALS SPECIFIED AS WASHED SHALL BE WASHED AND FREE OF FINES.



DETAIL B

CITY OF RALEIGH STANDARD DETAIL		
REVISIONS	DATE: 8/2020	NOT TO SCALE
		PERMEABLE PAVER PARKING LANE
		GSI-04