



SECTION VIEW

NOTES:

1. MATERIALS AND CONSTRUCTION OF PERMEABLE CONCRETE (PC) SHALL CONFORM TO THE FOLLOWING SPECIFICATIONS: MIX DESIGN (ACI 522.1); FRESH UNIT WEIGHTS AND VOIDS (ASTM C1688); FIELD INFILTRATION (ASTM C1701); RAVELING POTENTIAL (ASTM C1747); HARDENED UNIT WEIGHT AND VOID CONTENT (ASTM C1754).
2. RECOMMENDED VOIDS RATIO FOR PC IS 20% (15-25% ACCEPTABLE).
3. SLOPE OF SOIL SUBGRADE SHALL BE 0.5% OR LESS. MAXIMUM PC SURFACE SLOPE SHALL BE 6%.
4. THE SEASONAL HIGH WATER TABLE SHALL BE 2 FEET BELOW THE BOTTOM OF THE AGGREGATE BASE.
5. IN HSG B, C, OR D SOILS, THE SURFACE OF THE SUBGRADE SHOULD BE SCARIFIED, RIPPED, OR TRENCHED IMMEDIATELY PRIOR TO AGGREGATE SUBBASE PLACEMENT TO MAINTAIN PRE-CONSTRUCTION SUBGRADE INFILTRATION RATE.
6. THE INCLUSION OF AN UNDERDRAIN SYSTEM WITH IMPERMEABLE LINER (INCLUDING BOTTOM LAYER) IS DEPENDENT UPON THE RESULTS OF THE GEOTECHNICAL INVESTIGATION CONSISTENT WITH THE GUIDANCE PROVIDED IN THE NCDEQ STORMWATER DESIGN MANUAL AND CITY OF RALEIGH DESIGN MANUAL.
7. IF PERMEABLE RUNOFF DRAINS TO THE PC SIDEWALK, A VEGETATED CONVEYANCE DIVERSION SHALL BE INSTALLED UPGRADIENT AND SIZED FOR SAFE CONVEYANCE OF THE 10-YR, 24-HR STORM. CONVEYANCE DIVERSION SHALL DISCHARGE TO STORM DRAINAGE SYSTEM AND NOT ON OR ACROSS PC SIDEWALK.
8. IMPERMEABLE RUNOFF IS ALLOWED TO DRAIN TO THE PC SIDEWALK IN ACCORDANCE WITH DESIGN CRITERIA PROVIDED IN CHAPTER 18 OF THE NCDEQ STORMWATER DESIGN MANUAL.
9. ALL AGGREGATE SIZED ACCORDING TO ASTM C136.
10. IF REQUIRED BASED ON SITE CONDITIONS, INCLUDING SIGNIFICANT IMPERVIOUS RUN-ON VOLUMES, LOCATE UNDERDRAIN AS SHOWN ON THE IMPROVEMENT PLANS. HORIZONTAL LOCATION MAY VARY WITHIN PAVEMENT SECTION AS LONG AS MINIMUM OFFSET DISTANCES AND BOTTOM SLOPES ARE MAINTAINED. DEPTH OF PERFORATED PVC PIPE MAY BE ADJUSTED TO TIE INTO THE ADJACENT DRAINAGE INFRASTRUCTURE AS NEEDED.
11. ALL MATERIAL SPECIFIED AS WASHED SHALL BE WASHED AND FREE OF FINES.

CITY OF RALEIGH STANDARD DETAIL		
REVISIONS	DATE: 8/2020	NOT TO SCALE
		PERMEABLE CONCRETE SIDEWALK
		GSI-05