


TYPICAL NOTES:

- 1)-ALL PIPING AND FITTINGS TO BE DUCTILE IORN, GALVANIZED BRASS, STAINLESS STEEL, OR ALUMINIUM
- 2)-40' MAX. FROM FDC TO APPARATUS ACCESS LOCATION
- 3)-FDC TO FACE FIRE APPARATUS ACCESS LOCATION (DRIVEWAY)
- 4)-DO NOT BLOCK APPARATUS ACCESS TO BUILDING WITH HOSE LAY FROM HYDRANT TO FDC
- 5)-MINIMUM DISTANCE 3 FEET BEHIND CURB, PROTECT FROM VEHICLES
- 6)-PROVIDE HEAT AND ALARM SUPERVISION TO HOT BOX (2 CONDUITS)
- 7)-COMPLY WITH PUBLIC UTILITIES HANDBOOK REQUIREMENTS
- 8)-MAINTAIN ACCESS TO VALVE PIT



CITY OF RALEIGH FIRE DEPARTMENT
 FIRE PROTECTION DIVISION
 310 WEST MARTIN ST. RALEIGH, NC 27602

DESCRIPTION:
 RETROFIT BACKFLOW PREVENTER

REVISIONS:
 5-1-2017

DATE:
 4-1-06

DRAWING NO.
 FP-19